

ARMY PUBLIC SCHOOL

AHMEDABAD CANTT

Ph: 079-22862543

Fax No : 079 2286 0717
E-mail Id : apsahmedabad@gmail.com

3063/APS-AC/Const

16 Mar 2024


CALLING OF QUOTATION FOR CONSTRUCTION OF ROUNDEL AROUND TREE MALLAKHAMB PIT & ANTI SKID RAMP: ARMY PUBLIC SCHOOL AHMEDABAD CANTT

1. There is a reqmt to construct of roundel around tree, Mallakhamb pit & Anti skid ramp in the assembly ground as per details mentioned below:-

Ser No	Description	AU	Qty	Cost per Item	Total Cost
1	Surface Preparation:- Trimming, surfacing dressing, Filling, compaction and leveling of excavated earth not exceeding 100 mm for laying of successive layer.				
2	Pouring in position CC work in site mix cement concrete designed for M10 strength with 1:3:6 ratio of cement sand and aggregates leaving dowels as per required size and shape, provision of cutouts in slabs with consolidating with mechanical vibrators, curing by forming ponds, hacking the exposed surface to receive plaster.				
3	LDPE Polymer Sheet:- Laying in position LD Polymer Sheets of 200 Micron thickness as Vapour barrier on top of compacted subgrade of WMM PCC bed and below concrete floor to allow for Shrinkage, creep movement of floor.				
4	Constructing burnt brick masonry at all levels in cement mortar 1:6 for walls, steps, best quality available bricks in 1st class English bond including transoms and mullions, necessary scaffolding, raking out joints, curing.				
5	External sand faced cement plaster minimum 20 MM thick to the external surfaces of RCC & Masonry work in 2 coats, 1st coat of 12 MM thick in 1:4 proportion and 2nd coat of 8 MM thick in 1:3 proportion with waterproofing additive of Pidilite/ Fosroc/ Sunanda / Roff make and Nina fibers including RCC beams, grooves, bands, drip moulds, scaffolding, curing, scraping surface for 2nd coat.				
6	Excavation for the demarcated area for foundations of columns footings, walls, steps, ramps, etc. up to a depth of 300MM. including recording levels, shoring, strutting, refilling & compacting around walls, and footings.				
7	Carting material from the site Dispose of the material out of the premises.				

8	Laying 60" x 10" size granite stone for tree roundel with 15MM thickness in 1:4 Cement/sand mortar including material and labour				
9	Prov. & applying asian paint apex paint in desired shade/colour with surface preparation removing dust and loose particles, scratching old paint, priming, crack filling and two coat apex paint with all safety protocols for all height and levels.				
10	Providing and laying 4" x 15' size anti skid ramp with patti granite stone, 15MM thickness in 1:4 Cement/sand mortar including material and labour.				
TOTAL					

2. You are requested to submit quotation for aforesaid the project wk. Please ensure that your quotation reaches on school email id by **22 Mar 2024**.


 (Mrs Sangeeta Patel)
 Principal

Managed by Army Welfare Education Society (AWES)
Affiliated to CBSE Affiliation No 480004 (Old No. 430021) School No: 14001
(Nr. Hanuman Camp, Shahibhaug, Ahmedabad Cantt – 380 004)